

Real Estate Inspection Report



1234 Anywhere Dr Marco Island, FL 34145



Prepared for: Mr & Mrs Somebody 1234 Anywhere Dr

Table of Contents

Introduction	2
Definitions	2
General Information	2
Lots and Grounds	4
Exterior Surface and Components	6
Pool	7
Roof	10
Garage/Carport	12
Electrical	13
Plumbing	15
Attic	16
Air Conditioning	17
Fireplace/Wood Stove	19
Heating System	20
Laundry Room/Area	21
Bathroom	23
Bedroom	27
Living Space	29
Kitchen	30
Liabiliy/Disclaimer	32
Summary	34



Prepared for: Mr & Mrs Somebody 1234 Anywhere Dr

Introduction

To our client,

We would like to thank you for choosing Eyezon Home Inspectors to perform your personalized real estate property inspection. In the following pages you will find a comprehensive inspection report with a break-down of all required areas including photographs of particular areas that may or may not require immediate attention. This will be very helpful for you to use as a reference and hopefully aid you in making your real estate purchase decision. To make the Inspection Report easy to read and understand, we have placed photographs in both the Body and Summary sections of the report. The Summary section you will find located at the end of the inspection report and it will contain ALL of the MARGINAL and DEFECTIVE items found. If you have any questions or concerns after reading the report, PLEASE don't hesitate to call or email our office.

Again, Thank You!

We appreciate your business.

Sincerely, Bradley MacFarland, CPI

Eyezon Home Inspectors brad@eyezonhomeinspectors.com 239-776-8066

Definitions

NOTE: All definitions listed below refer to the property or item listed as inspected on this report at the time of inspection

Acceptable Functional with no obvious signs of defect.

Not Present Item not present or not found.

Not Inspected Item was unable to be inspected for safety reasons or due to lack of power, inaccessible, or disconnected at time of

inspection.

Marginal Item is not fully functional and requires repair or servicing.

Defective Item needs immediate repair or replacement. It is unable to perform its intended function.

General Information

Property Information

Property Address 1234 Anywhere Dr City Marco Island State FL Zip 34145 Contact Name John Doe

Client Information



Prepared for: Mr & Mrs Somebody 1234 Anywhere Dr

General Information (Continued)

Client Name Mr & Mrs Somebody Phone 239-555-5555 Fax . E-Mail Somebody@aol.cm

Inspection Company

Inspector Name Bradley MacFarland
Company Name Eyezon Home Inspectors
Address Eyezon Home Inspectors
City Naples State Florida Zip 34120
Phone 239-776-8066 Fax .
E-Mail brad@eyezonhomeinspectors.com
File Number M120718M

Conditions

Others Present Seller representative, Buyer's Agent and Buyer Property Occupied Vacant

Estimated Age 1988 Entrance Faces West

Inspection Date 01/32/2020

Amount Received \$550.00

Start Time 10:00 End Time 3:00

Electric On Yes

Gas/Oil On Not Applicable

Water On Yes

Temperature 75

Weather Sunny Soil Conditions Dry

Space Below Grade None

Building Type Single family Garage Attached

Sewage Disposal Septic How Verified Multiple Listing Service

Water Source Central How Verified Multiple Listing Service

Additions/Modifications N/A

Permits Obtained NOTE; Permit information is outside the scope of a Home Inspector or Home Inspection Report in the State of Florida. Further investigation by yourself, your real estate attorney or your Realtor is recommended. How Verified N/A



Prepared for: Mr & Mrs Somebody 1234 Anywhere Dr

Lots and Grounds

Note: Wood and vinyl sidings should be a minimum of 6" above ground. Detection of the presence of concealed moisture, mold or wood decay present behind exterior finishes is beyond the scope of this inspection. Promote positive (+) drainage away from foundation and extend runoff from roofing and downspouts a minimum 6 ft from foundation is always recommended. Irrigation wells, pumps, equipment, underground piping and sprinkler head functions are outside the scope of a home inspection per State of Florida SOP for Home Inspectors

NOTE: All definitions listed below refer to the property or item listed as inspected on this report at the time of inspection

Acceptable Functional with no obvious signs of defect.

Not Present Item not present or not found.

Not Inspected Item was unable to be inspected for safety reasons or due to lack of power, inaccessible, or disconnected at time of

inspection.

Marginal Item is not fully functional and requires repair or servicing.

Defective Item needs immediate repair or replacement. It is unable to perform its intended function.

1 Defective

Driveway: Stamped Concrete - Uneven settling, Heaves in concrete causing trip hazard, Damaged or deteriorated, recommend estimate for repair or replacement by a licensed contractor













2. Marginal, Defective Walks: Concrete - Soil erosion noted along edge of concrete slab on side of garage, slab is cracked, this should be replaced to prevent further undermining of surface and causing more damage to slab



3. Acceptable Porch: Travertine tile
4. Acceptable Lanai Textured Concrete



Prepared for: Mr & Mrs Somebody 1234 Anywhere Dr

Lots and Grounds (Continued)

5. Marginal

Grading: Minor slope - Soil erosion along sides of a/c slab , recommend adding fill and or grass to prevent further erosion or undermining possibly causing damage to exterior equipment



6. Acceptable

Swale: Adequate slope and depth for drainage

7. Acceptable, Marginal Vegetation: Sand/dirt, Weeds, Grass, trees and shrubs - several areas of lawn are brown or just dirt due to lack of water/maintenance

8. Defective

Lawn Sprinklers: Front and back yard - Inoperative at time of inspection, tested using manual mode of timer. Timer not tested, pump zone start relay appears to be defective and was making a loud buzzing noise. Sprinkler line(s) and or head damage noted, I recommend a qualified irrigation contractor go through entire sprinkler system, evaluate and or repair all that is needed for proper operation, adjust/repair all sprinkler heads, and educate the new homeowner of proper operation.















Prepared for: Mr & Mrs Somebody 1234 Anywhere Dr

Exterior Surface and Components

Note: Wood and vinyl sidings should be a minimum of 6" above ground. Detection of the presence of concealed moisture, mold or wood decay present behind exterior finishes is beyond the scope of this inspection. Promote positive (+) drainage away from foundation and extend runoff from roofing and downspouts a minimum 6 ft from foundation is always recommended.

NOTE: All definitions listed below refer to the property or item listed as inspected on this report at the time of inspection

Acceptable Functional with no obvious signs of defect.

Not Present Item not present or not found.

Not Inspected Item was unable to be inspected for safety reasons or due to lack of power, inaccessible, or disconnected at time of

inspection.

Marginal Item is not fully functional and requires repair or servicing.

Defective Item needs immediate repair or replacement. It is unable to perform its intended function.

Entire building Exterior Surface -

1. Acceptable Type: CBS

2. Acceptable Trim: Concrete, Foam

3. Marginal Fascia: Wood - Slight wood rot/water damage noted in a couple areas



4. Acceptable Soffits: Stucco with vent screens

5. Acceptable Door Bell: Button tested

6. Acceptable, Marginal Entry Doors: Wood - Wear noted, typical for age of wood door. needs

caulked and re-painted

7. Acceptable Patio Door: French with full view glass

8. Acceptable Windows: Aluminum crank, Non-opening

9. Not Present Window Screens: Several (almost ALL) windows are missing screens, check

with homeowner if screens being stored or are actually missing

10. Marginal Exterior Lighting: Surface mount, Surface mounted lamps, Hanging entry -

Loose light fixture , not secured to electrical box



11. Defective Exterior Electric Outlets: 110 VAC - Inoperative at time of inspection, Outlets have visible corrosion, Loose or missing moisture cover



Prepared for: Mr & Mrs Somebody 1234 Anywhere Dr

Exterior Surface and Components (Continued)

Exterior Electric Outlets: (continued)







Hose Bibs: Gate 12. Acceptable

Pool

Eyezon Home Inspectors will not inspect any underground equipment, pipes or structures, including pool equipment. It is unknown if any pool or underground equipment leak. Pool inspections are visual only. A licensed pool company is recommended to go through and evaluate complete system, label all valves and educate new homeowner of how system works.

NOTE: All definitions listed below refer to the property or item listed as inspected on this report at the time of inspection

Functional with no obvious signs of defect. Acceptable

Not Present Item not present or not found.

Not Inspected Item was unable to be inspected for safety reasons or due to lack of power, inaccessible, or disconnected at time of

inspection.

Item is not fully functional and requires repair or servicing. Marginal

Item needs immediate repair or replacement. It is unable to perform its intended function. Defective

Behind home Swimming Pool -

1. Marginal, Defective Type: In ground with spa - Blower for spa jets does not work, pump air jet adjustment cap on spa deck is missing. Appears that individual pump timers for spa and pool are tied into one main timer. Did not locate child safety screens for pool deck protection. Check with current owner if possible. A licensed pool company is recommended to go through and evaluate complete system and specify what all needs repaired for proper operation











2. Current Status: Partially Functional



Prepared for: Mr & Mrs Somebody 1234 Anywhere Dr

Pool (Continued)

3 Acceptable, Marginal Liner: Diamond Brite/PebbleTech - Appeared to be blotches or irregularities on pool lining surface, this may just be spots of dirt or debris and may just need good cleaning or chemical staining, further examination by a qualified pool tech is recommended as this is outside the scope of a Florida Licensed Home Inspector. Rust or water stains noted at spa jets on bottom of spa surface.



4. Defective

Pool Light Submersed - Pool and spa light did not come with switch, Water/rust stains noted at bottom of pool light. Further evaluation by a qualified pool tech is recommended



5. Acceptable

Deck: Textured concrete - Settlement cracks noted, recommend sealing all cracks to prevent moisture intrusion

6. Acceptable

Coping: Concrete

7. Acceptable

Drainage: Bottom main

8 Marginal

Missing skimmer flapper door, flapper door Skimmer: **Functioning** should be in place to prevent larger objects such as pool toys (balls) from entering skimmer and possibly blocking suction pump which would damage the pool pump itself







Prepared for: Mr & Mrs Somebody 1234 Anywhere Dr

Pool (Continued)

9. Marginal

Pump Motor: Century - Ground wire on pump is not connected, Air bubbles noted in the pumps strainer pot or filter basket this is generally caused from one of three things on the suction side of the pump. One - the pool water level being too low therefore sucking air through the strainer. Two - the rubber O ring in the pump connector coupler being bad or not correctly in place. Three - the clear plastic view cover on the strainer pot not secured tightly. Further evaluation recommended.



10. Acceptable Filter: Hayward

11. Acceptable, Marginal Shut-off Valve: Ball valves - No valve's are labeled for user to know what function they serve, Handle broken





12. Acceptable Back Wash Valve: Ball valves

13. Marginal, Defective Heater: Rheem - Not properly grounded, missing ground wire, Would not function, power light came on but did not appear to be heating. Further evaluation by a licensed pool tech is recommended.



14. Marginal Gauges and Controls: Hayward, Functioning - Broken cover, Damaged needs replaced








Prepared for: Mr & Mrs Somebody 1234 Anywhere Dr

Pool (Continued)

15. Not Present, Marginal Ladder/Steps: Stainless steel hanging, Built in step with handrail

- Hanging steps have been removed. built in step handrail is
loose, needs to be secured





16. Marginal

Pool Enclosure: Screen cage - Screen cage tension cables are loose and should be tightened. These cables help prevent the cage from moving in windy or bad weather conditions, when this happens it also stretches the screens causing them to become loose or torn. Pool cage door latch requires adjustment to open and close properly. Evidence of water leak noted at cage frame and gutter connection. Dry day unable to verify







Roof

I always recommend trimming tree limbs 6 ft. away from roof and cleaning debris off of roof and out of gutters at least a couple times a year to help prevent pre-mature wear and assure proper water discharge off of the roof and away from structure.

NOTE: All definitions listed below refer to the property or item listed as inspected on this report at the time of inspection

Acceptable Functional with no obvious signs of defect.

Not Present Item not present or not found.

Not Inspected Item was unable to be inspected for safety reasons or due to lack of power, inaccessible, or disconnected at time of

inspection.

Marginal Item is not fully functional and requires repair or servicing.

Defective Item needs immediate repair or replacement. It is unable to perform its intended function.

Main Roof Surface •

1. Method of Inspection: On roof











Prepared for: Mr & Mrs Somebody 1234 Anywhere Dr

Roof (Continued)

Method of Inspection: (continued)



2. Acceptable Material: Cement tile - Trees and shrubs should be trimmed back and off roof to prevent unnecessary or premature damage to roofing material



3. Type: **Hip**

4. Approximate Age: 2013

5. Acceptable Flashing: Peel and stick, Lead, Galvanized

6. Acceptable Valleys: Rolled roof material
7. Acceptable Plumbing Vents: Lead boots, PVC

8. Acceptable, Marginal Gutters: Aluminum, Boxed - Gutters have some debris (pine needles) in them. Periodic cleaning to maintain proper water flow is recommended, Dry day, unable to check for proper water flow, however no gutters were holding water when observed from roof





9. Acceptable

Downspouts: Aluminum

10. Marginal Leader/Extension: Missing or damaged - Some Splash blocks are missing.
installing splash blocks or leaders to move water away from foundation.







Prepared for: Mr & Mrs Somebody 1234 Anywhere Dr

Roof (Continued)

North side of home Chimney -

Unable to view interior of chimney due to height, photo 11 Acceptable Chimney: Block -







12. Acceptable, Not Inspected Flue/Flue Cap: Metal - Metal cap slightly dented, cosmetic only, probably got dented in hurricane. Chimney lining could not be inspected due to rain cap







Chimney Flashing: flashing covered up with stucco, and Cricket 13. Acceptable

Garage/Carport

The garage door is one of the largest moving objects in a home. Improperly installed safety eyes on the garage door is a main cause of property damage and bodily injury. Testing and monitoring the garage door's operation regularly is an important task related to home maintenance. Inspection does not cover any damage concealed by rugs, mats(floor coverings), wall paneling, personal or stored items. Typical wall/ceiling minor cracks/touch ups are considered normal and are not listed in report.

NOTE: All definitions listed below refer to the property or item listed as inspected on this report at the time of inspection

Acceptable Functional with no obvious signs of defect.

Not Present Item not present or not found.

Not Inspected Item was unable to be inspected for safety reasons or due to lack of power, inaccessible, or disconnected at time of

inspection.

Item is not fully functional and requires repair or servicing. Marginal

Defective Item needs immediate repair or replacement. It is unable to perform its intended function.

Front of home Garage -

1. Type of Structure: Attached Car Spaces: 2

2 Acceptable Garage Doors: Insulated aluminum







Prepared for: Mr & Mrs Somebody

1234 Anywhere Dr

Garage/Carport (Continued)

3. Acceptable Door Operation: Mechanized
4. Acceptable Door Opener: Lift Master
5. Acceptable Exterior Surface: Stucco

6. Marginal Service Doors: Fiberglass with wood core - Entry door not rated for fire,

door should be Solid Wood or Metal and preferably have a self closing

hinge installed for safety reasons

7. Acceptable Ceiling: Paint 8. Acceptable Walls: Paint 9. Not Inspected House Vac

10. Acceptable Floor/Foundation: Poured concrete





11. Acceptable Electrical: 110 VAC GFCI

12. Acceptable, Not Inspected Windows: Wood casement - The window will not open due to hurricane panel hardware installed



Electrical

Testing of smoke detectors or alarms, timers, low voltage circuits such as door bells, security, home audio and pet containment systems are beyond the scope of this inspection. Smoke detectors are recommended to be located in each bedroom and one per floor level. Smoke alarms should be tested monthly and replaced per manufacturers guidelines or every 10 years. Recommend grounded and GFCI protected outlets be installed at all Exterior, Kitchen, Wet Bar and Garage outlet locations if not so equipped.



Prepared for: Mr & Mrs Somebody

1234 Anywhere Dr

Electrical (Continued)

NOTE: All definitions listed below refer to the property or item listed as inspected on this report at the time of inspection

Acceptable Functional with no obvious signs of defect.

Not Present Item not present or not found.

Not Inspected Item was unable to be inspected for safety reasons or due to lack of power, inaccessible, or disconnected at time of

inspection.

Marginal Item is not fully functional and requires repair or servicing.

Defective Item needs immediate repair or replacement. It is unable to perform its intended function.

1. Service Size Amps: 200 Volts: 110-240 VAC

2. Acceptable Service: Under ground service entrance



3. Acceptable4. Acceptable240 VAC Branch Circuits: Copper240 VAC Branch Circuits: Copper

5. Acceptable Aluminum Wiring: HVAC, Pool pump

6. Acceptable Conductor Type: Non-metallic sheathed cable

7. Acceptable Ground: Rod in ground

Garage Electric Panel

8. Acceptable Manufacturer: I-T-E - Photo showing inspection of open electrical panel





9. Maximum Capacity: **200 Amps, At meter**10. **Acceptable** Main Breaker Size: **200 Amps**

11. Acceptable Breakers: Copper

12. Not Present Fuses: 13. Not Present AFCI:

14. Acceptable GFCI: At GFCI receptacles only

15. Is the panel bonded? Yes



Prepared for: Mr & Mrs Somebody 1234 Anywhere Dr

Plumbing

Water heater, plumbing fixtures and connectors tested for functional operation at time of inspection only. Appliance thermostats, timers and other specialized features and controls are not tested. The temperature calibration, functionality of timers, effectiveness, efficiency and overall performance of appliances is outside the scope of this inspection. No life expectancy is expressed or implied, as any of these components can fail at anytime. NACHI SOP: The inspector shall run water in sinks, tubs and showers. NACHI SOP: The inspector is not required to operate any main, branch or fixture valves. If home is equipped with, I always suggest having the well equipment, water softening system and septic system inspected and or serviced by a professional company and educate the owner of condition and proper operation of such. Wells, Septic and Water conditioning/filtering systems are not within the scope of this inspection.

NOTE: All definitions listed below refer to the property or item listed as inspected on this report at the time of inspection

Acceptable Functional with no obvious signs of defect.

Not Present Item not present or not found.

Not Inspected Item was unable to be inspected for safety reasons or due to lack of power, inaccessible, or disconnected at time of

inspection.

Marginal Item is not fully functional and requires repair or servicing.

Defective Item needs immediate repair or replacement. It is unable to perform its intended function.

1. Acceptable Service Line: PVC and copper

2. Acceptable Main Water Shutoff: Side of garage - Location photo of Main water shut off



3. Acceptable Water Lines: Copper 4. Acceptable Drain Pipes: PVC

5. Acceptable Service Caps: Accessible - Location of clean out/service cap



6. **Acceptable**Garage Water Heater -

Vent Pipes: PVC

7. Acceptable

Water Heater Operation: Functional at time of inspection - Date code of 2010 on ID Plate, Water heater is nearing the end of it's design life, Manufacturers designed life expectancy is approx. 10 years





8. Manufacturer: General Electric





Prepared for: Mr & Mrs Somebody

1234 Anywhere Dr

Plumbing (Continued)

9. Model Number: GE50M06AAG Serial Number: 0410B14500

10. Type: Electric Capacity: 50 Gal.

11. Approximate Age: **2010** Area Served: **Living area**12. **Acceptable** TPRV and Drain Tube: **Copper**

Attic

Some attic areas are not accessible due to low clearance and insulation. Inaccessible areas, including areas covered by insulation, equipment or storage items which the inspector must move or deface will not be inspected and therefore no opinion will be rendered.

NOTE: All definitions listed below refer to the property or item listed as inspected on this report at the time of inspection

Acceptable Functional with no obvious signs of defect.

Not Present Item not present or not found.

Not Inspected Item was unable to be inspected for safety reasons or due to lack of power, inaccessible, or disconnected at time of

inspection.

Marginal Item is not fully functional and requires repair or servicing.

Defective Item needs immediate repair or replacement. It is unable to perform its intended function.

Garage Attic -

1. Method of Inspection: In the attic



2. Acceptable Unable to Inspect: Some of - Roof line, Safety and footing, Insulation, Limited access







Acceptable
 Acceptable

Roof Framing: 2x6, 2x4 Truss

Sheathing: Unknown, covered with spray foam insulation



5. Acceptable

Ventilation: Roof and soffit vents - Metal roof vent appears to have been dented from storm but does not appear to effect function.



Prepared for: Mr & Mrs Somebody

1234 Anywhere Dr

Attic (Continued)

6. Acceptable

Insulation: Closed cell foam



7. Acceptable

Insulation Depth: 6"

Wiring/Lighting: 110 VAC lighting circuit 8. Acceptable

9 Not Present

Moisture Penetration:

10. Acceptable

Bathroom Fan Venting: Electric fan





Air Conditioning

Mechanical equipment tested for functional operation at time of inspection only. No life expectancy is expressed or implied. Inspection does not determine balancing or sizing of system. The inspection covers only the visible components of the air conditioning system. Hidden problems may exist that are not documented in this report. Annual cleaning / servicing before the heavy use or "HOT" season by a licensed A/C contractor is recommended to assure proper function, efficiency and life expectancy of the system(s). Manufacturers expected life expectancy with proper maintenance is 15-20 years. Coastal environments can drastically reduce life expectancy.

NOTE: All definitions listed below refer to the property or item listed as inspected on this report at the time of inspection

Acceptable Functional with no obvious signs of defect.

Not Present Item not present or not found.

Not Inspected Item was unable to be inspected for safety reasons or due to lack of power, inaccessible, or disconnected at time of

inspection.

Marginal Item is not fully functional and requires repair or servicing.

Defective Item needs immediate repair or replacement. It is unable to perform its intended function.

Main #1 AC System •

1. Acceptable

2. Acceptable

3. Acceptable

A/C System Operation: Functioning at time of inspection

Condensate Removal: PVC

Location and ID photo for condensing unit, Exterior Unit: On concrete -

2012 mfg date (code) on outside condenser ID plate







Prepared for: Mr & Mrs Somebody 1234 Anywhere Dr

Air Conditioning (Continued)

4. Manufacturer: Lennox

5. Model Number: XC13-047-230-02 Serial Number: 5812C05384

6. Area Served: Living area Approximate Age: 2012

7. Fuel Type: 220-240 VAC Temperature Differential: 19 degree

8. Type: Central A/C Capacity: 4 Ton

9. Acceptable Visible Coil: Copper core with aluminum fins
10. Acceptable Refrigerant Lines: Suction line and liquid line

11. Acceptable Electrical Disconnect: General Duty Pull



Side of building AC System

12. Acceptable A/C System Operation: Functioning at time of inspection

13. Acceptable Condensate Removal: PVC

14. Acceptable Exterior Unit: Concrete mounted



15. Manufacturer: **Lennox**

16. Model Number: XC14-018-230-04 Serial Number: 5813H11968

17. Area Served: Master Approximate Age: 2013

18. Fuel Type: 220-240 VAC Temperature Differential: 20 degree

19. Type: Central A/C Capacity: 1.5 Ton

20. Acceptable Visible Coil: Copper core with aluminum fins

21. Acceptable Refrigerant Lines: Suction line and liquid line

22. Acceptable Electrical Disconnect: General Duty Pull



23. Acceptable Blower Fan/Filters: Visually functional



Prepared for: Mr & Mrs Somebody

1234 Anywhere Dr

Air Conditioning (Continued)

24 Acceptable



Fireplace/Wood Stove

Chimney flue inspection is limited due to height. The inspection covers only the visible portion of the flue. Most fireplaces in Florida are not often used and may have acquired cracks, obstructions or animals in flue. A full inspection of the chimney flue by a certified chimney company is recommended before using fireplace. (Safety Issue)

NOTE: All definitions listed below refer to the property or item listed as inspected on this report at the time of inspection

Functional with no obvious signs of defect. Acceptable

Not Present Item not present or not found.

Not Inspected Item was unable to be inspected for safety reasons or due to lack of power, inaccessible, or disconnected at time of

inspection.

Marginal Item is not fully functional and requires repair or servicing.

Defective Item needs immediate repair or replacement. It is unable to perform its intended function.

Family Room Fireplace

1. Acceptable

Fireplace Construction: Block



2. Type: Wood burning

3. Acceptable Fireplace Insert: Standard



Smoke Chamber: Fire Brick 4. Acceptable

Flue: Tile 5. Acceptable



Prepared for: Mr & Mrs Somebody 1234 Anywhere Dr

Fireplace/Wood Stove (Continued)

6 Defective

Damper: Metal - Damper latch is missing or broken, cannot secure damper in closed position to prevent conditioned air in home from escaping through chimney flue when not in use



7 Acceptable

Hearth: Raised, Tile

Heating System

Mechanical equipment tested for functional operation at time of inspection only. No life expectancy is expressed or implied. The inspection covers only the visible components of the heating system. Hidden problems may exist that are not documented in this report. Annual cleaning and servicing recommended for best performance and life expectancy. According to ENERGY.GOV/Dept of Energy The "lifespan" of a central air conditioner is about 15 to 20 years.

NOTE: All definitions listed below refer to the property or item listed as inspected on this report at the time of inspection

Acceptable Functional with no obvious signs of defect.

Not Present Item not present or not found.

Not Inspected Item was unable to be inspected for safety reasons or due to lack of power, inaccessible, or disconnected at time of

inspection.

Marginal Item is not fully functional and requires repair or servicing.

Defective Item needs immediate repair or replacement. It is unable to perform its intended function.

Main #1 Heating System -

1. Acceptable Heating System Operation: Appears functional - 2013 mfg date (code) on air handler ID plate

2. Manufacturer: **Lennox**





- 3. Model Number: CBX27UH048230603 Serial Number: 1613F03051
- 4. Type: Forced air Capacity: 208/240vac with electric strip
- 5. Area Served: Main house Approximate Age: 2013
- 6. Fuel Type: Electric
- 7. Unable to Inspect: Some of duct due to limited or no access
- 8. Acceptable Blower Fan/Filter: Fan visually functional
- 9. Acceptable Distribution: Insulated stack, Insulflex duct



Prepared for: Mr & Mrs Somebody

1234 Anywhere Dr

Heating System (Continued)

Attic Heating System

10. Acceptable

Heating System Operation: Appears functional - Location photo and ID information plate of Air Handler, 2013 mfg date (code) on air handler ID plate





11. Manufacturer: Lennox

12. Model Number: CBX27UH-018-230-6-02 Serial Number: 1613G10279

13. Type: Forced air Capacity: 208/240vac with electric strip

14. Area Served: Master side of home Approximate Age: 2013

15. Fuel Type: Electric

16. Unable to Inspect: Some of duct due to limited or no access

17. Acceptable Blower Fan/Filter: Visually functional

18. Acceptable Distribution: Insulflex duct, Insulated stack

19. Acceptable Thermostats: Programmable





20. Suspected Asbestos: No

Laundry Room/Area

Appliances are tested for functional operation at time of inspection only. Appliances thermostats, timers and other specialized features and controls are not tested.

The temperature calibration, functionality of timers, effectiveness, efficiency and overall performance of appliances is outside the scope of this inspection.

No life expectancy is expressed or implied. I recommend dryer venting system be further inspected and or freshly cleaned to start fresh and then be cleaned at least once a year as a part of homes regular maintenance. Inspection does not cover any damage concealed by rugs, carpet, paneling or stored items. Typical wall/ceiling minor cracks/touchups are considered normal and are not listed in report.

NOTE: All definitions listed below refer to the property or item listed as inspected on this report at the time of inspection

Acceptable Functional with no obvious signs of defect.

Not Present Item not present or not found.

Not Inspected Item was unable to be inspected for safety reasons or due to lack of power, inaccessible, or disconnected at time of

inspection.

Marginal Item is not fully functional and requires repair or servicing.

Defective Item needs immediate repair or replacement. It is unable to perform its intended function.



Prepared for: Mr & Mrs Somebody 1234 Anywhere Dr

Laundry Room/Area (Continued)

Inside main Laundry Room/Area -

1. Acceptable Closet: Built in cabinets

2. Acceptable Ceiling: Paint 3. Acceptable Walls: Paint



4. Acceptable

Floor: Tile

5. Acceptable

Doors: Hollow wood, UPVC/Fiberglass

6. Acceptable

Electrical: 110 VAC lighting

7. Acceptable

HVAC Source: Air exchange ventilation

8. Acceptable

Washer/Dryer Matching Front Loaders, Whirlpool, Used appliances - Tested by running wash and rinse cycle for drain function and Hot and Cold function. Ran dryer for a minute to test for heat and venting ONLY



9. Marginal

Laundry Tub: PVC - No hot water only warm, requires further review



10. Acceptable

Laundry Tub Drain: PVC





Prepared for: Mr & Mrs Somebody

1234 Anywhere Dr

Laundry Room/Area (Continued)

11 Acceptable

Washer Hose Bib: Rotary



12. Acceptable

Washer and Dryer Electrical: 110-240 VAC

13. Acceptable

Dryer Vent: Metal flex

14. Acceptable

Washer Drain: Wall mounted drain

Bathroom

Inspection does not cover any damage concealed by rugs, carpet, wall paneling, personal or stored items. Typical wall/ceiling minor cracks/touch ups are considered normal and are not listed in report. Plumbing fixtures and connectors tested for functional operation at time of inspection only. No life expectancy is expressed or implied, as any of these components can fail at anytime. NACHI SOP: The inspector shall run water in sinks, tubs and showers.

NOTE: All definitions listed below refer to the property or item listed as inspected on this report at the time of inspection

Acceptable Functional with no obvious signs of defect.

Not Present Item not present or not found.

Not Inspected Item was unable to be inspected for safety reasons or due to lack of power, inaccessible, or disconnected at time of

inspection.

Marginal Item is not fully functional and requires repair or servicing.

Defective Item needs immediate repair or replacement. It is unable to perform its intended function.

Pool bath Bathroom •

1. Acceptable

Ceiling: Paint

2. Acceptable Walls: Paint and tile



3. Acceptable

Floor: Tile

4. Acceptable

Doors: Pocket slider, Metal with glass

5. Marginal W

Windows: Wood casement - The window will not open, blocked with shutters









Prepared for: Mr & Mrs Somebody 1234 Anywhere Dr

Bathroom (Continued)

6. Acceptable Electrical: 110 VAC GFCI

7. Acceptable Counter/Cabinet: Granite and wood

8. Acceptable Sink/Basin: Porcelain coated, Under mount

9. Acceptable Faucets/Traps: Glacier Bay fixture with PVC trap





10. Acceptable, Marginal Shower/Surround: Tile pan and tile surround - Cracked grout in corners of shower surround, this is typical of cement based grout being used for corner applications due to expansion and contraction. Recommend replacing with grout "caulk" to help prevent moisture intrusion. Grout caulk can be located in the tile section at most hardware stores



11. Acceptable Toilets: Pegasus

12. Acceptable HVAC Source: Air exchange ventilation

13. Acceptable Ventilation: Electric ventilation fan and window

Guest/Hallway Bathroom

14. Acceptable Ceiling: Paint

15. Acceptable Walls: Paint and tile



16. Acceptable

Floor: Tile

17. Acceptable

Doors: Hollow wood
Electrical: 110 VAC GFCI

18. Acceptable 19. Acceptable

Counter/Cabinet: Granite and wood

20. Acceptable

Sink/Basin: Porcelain coated, Under mount



Prepared for: Mr & Mrs Somebody 1234 Anywhere Dr

Bathroom (Continued)

21. Acceptable Faucets/Traps: Pegasus, PVC trap





22. Acceptable, Marginal Shower/Surround: Tile pan and tile surround - Cracked grout in corners of shower surround, this is typical of cement based grout being used for corner applications due to expansion and contraction. Recommend replacing with grout "caulk" to help prevent moisture intrusion. Grout caulk can be located in the tile section at most hardware stores



23. Acceptable Toilets: Kohler

24. Acceptable HVAC Source: Air exchange ventilation 25. Acceptable Ventilation: Electric ventilation fan

Master Bathroom -

26. Acceptable Ceiling: Paint

27. Acceptable Walls: Paint and tile





28. Acceptable Floor: Tile

29. Acceptable Doors: Hollow wood, Pocket slider, Bi-fold

30. Acceptable Windows: Glass block, Non-opening

31. Acceptable Electrical: 110 VAC GFCI

32 Acceptable Counter/Cabinet: Granite and wood

33. Acceptable Sink/Basin: Porcelain coated, Under mount



Prepared for: Mr & Mrs Somebody 1234 Anywhere Dr

Bathroom (Continued)

34 Acceptable

Faucets/Traps: Glacier Bay fixture with PVC trap









35. Marginal, Defective Shower/Surround: Tile pan and tile surround - Cracked grout in corners of shower surround, this is typical of cement based grout being used for corner applications due to expansion and contraction. Recommend replacing with grout "caulk" to help prevent moisture intrusion. Grout caulk can be located in the tile section at most hardware stores, Steamer for shower was not in use at time of inspection. Note on main electrical panel to leave steamer breaker in OFF position. Steam unit is located in attic. Touch control pad in bathroom shower shows signs of corrosion. Further evaluation by a licensed plumbing contractor is recommended.

















36. Acceptable

Toilets: Kohler

37. Acceptable 38. Acceptable

HVAC Source: Air exchange ventilation Ventilation: Electric ventilation fan



Prepared for: Mr & Mrs Somebody 1234 Anywhere Dr

Bedroom

Inspection does not cover any window coverings or window treatments and damage or defects concealed by rugs, carpeting, paneling, furniture, fixtures or stored items. Typical wall/ceiling minor cracks/touch ups are considered normal and are not listed in report.

NOTE: All definitions listed below refer to the property or item listed as inspected on this report at the time of inspection

Acceptable Functional with no obvious signs of defect.

Not Present Item not present or not found.

Not Inspected Item was unable to be inspected for safety reasons or due to lack of power, inaccessible, or disconnected at time of

nspection.

Marginal Item is not fully functional and requires repair or servicing.

Defective Item needs immediate repair or replacement. It is unable to perform its intended function.

Master Suite, Attached baby room/office Bedroom -

1. Acceptable Closet: Single
2. Acceptable Ceiling: Paint
3. Acceptable Walls: Paint





4. Acceptable

Floor: Wood Laminate, Tile

5. Marginal

Doors: Hollow wood, Bi-fold, Pocket slider - Lock/latch on bottom of French door does not work, left side of door cannot be opened. May just need to be cleaned and lubricated. Requires further review



6. Marginal

Windows: Wood casement, Non-opening - The window will not open, blocked by shutter or shutter hardware



7. Acceptable

Electrical: 110 VAC

8. Acceptable

HVAC Source: Air exchange ventilation

9. Not Inspected Smoke Detector: Present



Prepared for: Mr & Mrs Somebody 1234 Anywhere Dr

Bedroom (Continued)

Left front guest Bedroom -

10. Acceptable Closet: Single
11. Acceptable Ceilling: Paint
12. Acceptable Walls: Paint



13. Acceptable Floor: Wood Laminate

14. Acceptable Doors: Hollow wood, Bi-fold

15. Defective Windows: Wood casement - Will not open-requires correction, window crank

is broken







16. Acceptable Electrical: 110 VAC

17. Acceptable HVAC Source: Air exchange ventilation

18. Not Inspected Smoke Detector: Present

Left rear quest Bedroom

19. Acceptable Closet: Walk In 20. Acceptable Ceiling: Paint Walls: Paint



22. Acceptable Floor: Wood Laminate
23. Acceptable Doors: Hollow wood

24. Acceptable Windows: Wood casement

25. Acceptable Electrical: 110 VAC

26. Acceptable HVAC Source: Air exchange ventilation

27. Not Inspected Smoke Detector: Present



Prepared for: Mr & Mrs Somebody 1234 Anywhere Dr

Living Space

Inspection does not cover any window coverings or window treatments and damage or defects concealed by rugs, carpeting, paneling, furniture, fixtures or stored items. Typical wall/ceiling minor cracks/touch ups are considered normal and are not listed in report.

NOTE: All definitions listed below refer to the property or item listed as inspected on this report at the time of inspection

Acceptable Functional with no obvious signs of defect.

Not Present Item not present or not found.

Not Inspected Item was unable to be inspected for safety reasons or due to lack of power, inaccessible, or disconnected at time of

nspection.

Marginal Item is not fully functional and requires repair or servicing.

Defective Item needs immediate repair or replacement. It is unable to perform its intended function.

Living room, family room, dining room hallway and entry Living Space -

1. Acceptable Ceiling: Paint
2. Acceptable Walls: Paint





3. Acceptable, Not Inspected Wet Bar Sink with faucet, mini fridge - Refrigerator was not turned on at time of inspection, but did turn on with switch. No verification of cooling ability could be determined due to time allotted for inspection.







4. Acceptable Floor: Tile

5. Acceptable Doors: Wood entry, French full view glass

6. Acceptable Windows: Wood casement

7. Acceptable Electrical: 110 VAC

8. Acceptable HVAC Source: Air exchange ventilation

9. Not Inspected Smoke Detector: Present

Lanai Living Space -

10. Acceptable Ceiling: Paint 11. Acceptable Walls: Stucco







Prepared for: Mr & Mrs Somebody

1234 Anywhere Dr

Living Space (Continued)

12. Acceptable Floor: Textured concrete

13. Acceptable Screen enclosure Vinyl mesh, Aluminum

14. Acceptable Electrical: 110 VAC GFCI

Kitchen

Appliances are tested for functional operation at time of inspection only. Appliances thermostats, timers and other specialized features and controls are not tested.

The temperature calibration, functionality of timers, effectiveness, efficiency and overall performance of appliances is outside the scope of this inspection.

No life expectancy is expressed or implied. Inspection does not cover any damage concealed by rugs, carpet, paneling, kitchen furniture or stored kitchen items. Typical wall/ceiling minor cracks/touchups are considered normal and are not listed in report.

NOTE: All definitions listed below refer to the property or item listed as inspected on this report at the time of inspection

Acceptable Functional with no obvious signs of defect.

Not Present Item not present or not found.

Not Inspected Item was unable to be inspected for safety reasons or due to lack of power, inaccessible, or disconnected at time of

inspection.

Marginal Item is not fully functional and requires repair or servicing.

Defective Item needs immediate repair or replacement. It is unable to perform its intended function.

Main Kitchen and Breakfast nook area Kitchen -

1. Acceptable Cooking Appliances: Kichenaid - All burners tested good



2. Acceptable

Ventilator: KitchenAid



3. Acceptable

Disposal: In-Sinkerator





Prepared for: Mr & Mrs Somebody 1234 Anywhere Dr

Kitchen (Continued)

4. Acceptable

Dishwasher: KitchenAid - Ran dishwasher in Normal wash cycle to test for water leaks, operation and draining ability





5. Air Gap Present? Yes

6. Acceptable

Refrigerator: KitchenAid - Door seals, interior trays and shelving appeared to be intact at time of inspection



7. Acceptable

Microwave: KitchenAid



8. Acceptable

Sink: Stainless Steel, Under mount

9. Acceptable

Electrical: 110 VAC GFCI

10. Acceptable

Plumbing/Fixtures: Stainless Steel, PVC







11. Acceptable

Counter Tops: Granite, Granite



Prepared for: Mr & Mrs Somebody

1234 Anywhere Dr

Kitchen (Continued)

Counter Tops: (continued)



12. Acceptable

Cabinets: Wood



Pantry: Closet 13. Acceptable 14 Acceptable Ceiling: Paint Walls: Paint 15. Acceptable 16. Acceptable Floor: Tile 17. Acceptable Doors: Bi-fold

Windows: Aluminum slider, Aluminum slider 18. Acceptable

19. Acceptable HVAC Source: Air exchange ventilation

Liabiliy/Disclaimer

CONFIDENTIAL REPORT

The written report to be prepared by the Inspector shall be considered the final and exclusive findings of the Inspector/Eyezon Home Inspectors regarding the home inspection at the Inspection Address. The inspection report to be prepared for the Client is solely and exclusively for the Client's own information and may not be relied upon by any other person. Client agrees to maintain the confidentiality of the inspection report and agrees not to disclose any part of it to any other person with the exception of the seller and/or the real estate agents directly involved in this transaction. Client(s) or the inspector may distribute copies of the inspection report to the seller and real estate agents directly involved in this transaction, but neither the seller nor the real estate agent are intended beneficiaries of this Agreement or the Inspection Report. Client agrees to indemnify, defend and hold the Inspector/Eyezon Home Inspectors harmless from any third party claims arising out of the Client(s) or Inspectors distribution of the inspection report.

SCOPE OF INSPECTION

A general home inspection is a non-invasive, visual examination of the accessible areas of a residential property, performed for a fee, which is designed to identify defects within specific systems and components that are both observed and deemed material by the inspector. It is based on observations made on the date of inspection only, and not a prediction of future conditions. Nor are any warranties implied. It is a snapshot in time and is valid only for the date and time the inspection was performed. A general home installed will not reveal every issue that exists or ever could exist, but only those material defects observed on the date of inspection. A material defect is a specific issue with a system or component of a residential property that may have a significant, adverse impact on the value of the property, or that poses an unreasonable risk to people. The fact that a system or component is near, at, or beyond the end of its normal, useful life is not, in itself, a material defect.

OUTSIDE THE SCOPE OF THE INSPECTION

The inspection does not include any destructive testing or dismantling. Client agrees to assume all the risks for all conditions which are concealed from view at time of inspection. THIS IS NOT A HOME WARRANTY, GUARANTEE, INSURANCE POLICY OR SUBSTITUTE FOR REAL ESTATE DISCLOSURES WHICH MAY BE REQUIRED BY LAW

This report is based upon what was accessible and/or visual during the inspection. Areas, which are enclosed, covered with insulation or inaccessible including areas covered by wall coverings, floor coverings, furniture, equipment, storage items or any portion of any structure which



Prepared for: Mr & Mrs Somebody

1234 Anywhere Dr

Liabiliy/Disclaimer (Continued)

the inspector must move or deface, or lack of sufficient access will not be inspected and therefore no opinion will be rendered.

Latent condition may exist at this property that may not be observable and/or manifest at the time of the inspection. The client, upon acceptance of this report, agrees to hold Eyezon Home Inspectors harmless should such conditions occur after the inspection.

Eyezon Home Inspectors are not licensed roof contractors. If the buyer deems it necessary, they should hire a licensed roofing specialist to conduct an inspection in connection with codes, installation and longevity of roof. Eyezon Home Inspectors provides the opinion of a basic visual inspection, concerning the condition of the roof at the time of inspection. Any indication of marginal findings should prompt buyers to consider an additional inspection by roofing professional.

Eyezon Home Inspectors will not inspect any underground equipment, pipes or structures, including pool equipment. It is unknown if any pool or underground equipment leak. Eyezon Home Inspectors will inspect lawn sprinkler systems for functionality at the time of the inspection but will not inspect each sprinkler head. If the buyer requires a detailed sprinkler system inspection we suggest the buyer contact a licensed lawn maintenance company for this inspection.

This inspection is an inspection for purpose of informing the buyer or seller of the visual condition and functionality of components and systems of the home. Eyezon Home Inspectors does not make repairs or provide estimates for repairs of your property.

When an item is described as "marginal" it should be understood that this item needs repair. It may be functioning at the time of the inspection. However, it may be at or near its life expectancy and under normal circumstances may require maintenance, repair or replacement at anytime.

If the buyer is concerned with water intrusion in the past or present, or leaks or water spots of any kind, the buyer should employ the services of a specialist in infrared thermal imaging in order to accurately detect the presence of moisture in walls or areas that are inaccessible or visible or if an area has been cleaned of surface evidence. Eyezon Home Inspectors cannot detect moisture in walls or areas that are inaccessible or visible or if an area has been cleaned of surface evidence.

Electrical Service/Sub panel inspections are cursory in scope and intent. Only remedial circuit tests were performed in order to validate operation. A more extensive, critical and analytical evaluation would require the services of a State licensed electrician. Lighting that does not work will be assumed to be a defective bulb. Eyezon Home Inspectors does not exchange bulbs to test the socket. Switches/receptacles are subject to malfunction at anytime. Code violations and wiring conditions are not a part of this inspection.

DISPUTES

INSPECTORS LIABILITY FOR ANY MISTAKE, OMISSION, LOSS, OR DAMAGE ARISING OUT OF ANY ACT OR NEGLECT OF INSPECTOR, AGENT, OFFICER OR EMPLOYEE OF EYEZON HOME. INSPECTORS IN THE PERFORMANCE OF THIS CONTRACT SHALL BE LIMITED SOLELY TO A REFUND OF THE FEE PAID FOR THE VISUAL INSPECTION AND "INSPECTORS" REPORT. CLIENT UNDERSTANDS AND AGEES THAT ANY CLAIM OF FAILURE IN THE ACCURACY OF THE REPORT SHALL REPORTED TO THE INSPECTOR/EYEZON HOME INSPECTORS WITHIN FIVE BUSINESS DAYS OF DISCOVERY AND THAT FAILURE TO NOTIFY THE INSPECTOR/EYEZON HOME INSPECTORS WITHIN THAT TIME PERIOD SHALL CONSTITUTE A WAIVER OF ANY AND ALL CLAIMS. INSPECTOR/EYEZON HOME INSPECTORS SHALL HAVE FIVE BUSINESS DAYS TO RESPOND TO THE CLAIM. IF THE INSPECTOR /EYEZON HOME INSPECTORS FAILS TO SATISFY THE CLAIM, ABILITY SHALL AGAIN BE LIMITED TO THE PRICE/FEE PAID FOR THE INSPECTION AND REPORT.

ADDED NOTE:

If you're reading this report but did not hire me, Eyezon Home Inspectors, to perform the original inspection, please note that it is likely that conditions related to the home have probably changed, even if the report is fairly recent. Just as you cannot rely on an outdated weather report, you should not rely on an outdated inspection report. Minor problems noted may have become worse, recent events may have created new issues, and items may even have been corrected and improved. Don't rely on old information about one of the biggest purchases you'll ever make. Remember that the cost of a home inspection is insignificant compared to the value of the home. Protect your family and your investment, and please call me directly at (239)776-8066 to discuss the report you're reading for this property so that we can arrange for a re-inspection. Thank you!

NOTE: All definitions listed below refer to the property or item listed as inspected on this report at the time of inspection

Acceptable Functional with no obvious signs of defect.

Not Present Item not present or not found.

Not Inspected Item was unable to be inspected for safety reasons or due to lack of power, inaccessible, or disconnected at time of

inspection.

Item is not fully functional and requires repair or servicing. Marginal

Item needs immediate repair or replacement. It is unable to perform its intended function. Defective



Prepared for: Mr & Mrs Somebody 1234 Anywhere Dr

Marginal Summary

This summary is not the entire report. The complete report may include additional information of concern to the client. It is recommended that the client read the complete report.

Lots and Grounds

1. Walks: Concrete - Soil erosion noted along edge of concrete slab on side of garage, slab is cracked, this should be replaced to prevent further undermining of surface and causing more damage to slab



 Grading: Minor slope - Soil erosion along sides of a/c slab , recommend adding fill and or grass to prevent further erosion or undermining possibly causing damage to exterior equipment



3. Vegetation: Sand/dirt, Weeds, Grass, trees and shrubs - several areas of lawn are brown or just dirt due to lack of water/maintenance

Exterior Surface and Components

4. Fascia: Wood - Slight wood rot/water damage noted in a couple areas



- 5. Entry Doors: Wood Wear noted, typical for age of wood door. needs caulked and re-painted
- 6. Exterior Lighting: Surface mount, Surface mounted lamps, Hanging entry Loose light fixture, not secured to electrical box



Prepared for: Mr & Mrs Somebody 1234 Anywhere Dr

Exterior Surface and Components (Continued)



Pool

7. Behind home Swimming Pool Type: In ground with spa - Blower for spa jets does not work, pump air jet adjustment cap on spa deck is missing. Appears that individual pump timers for spa and pool are tied into one main timer. Did not locate child safety screens for pool deck protection. Check with current owner if possible. A licensed pool company is recommended to go through and evaluate complete system and specify what all needs repaired for proper operation












8. Behind home Swimming Pool Liner: Diamond Brite/PebbleTech - Appeared to be blotches or irregularities on pool lining surface, this may just be spots of dirt or debris and may just need good cleaning or chemical staining, further examination by a qualified pool tech is recommended as this is outside the scope of a Florida Licensed Home Inspector. Rust or water stains noted at spa jets on bottom of spa surface.



9. Behind home Swimming Pool Skimmer: Functioning - Missing skimmer flapper door, flapper door should be in place to prevent larger objects such as pool toys (balls) from entering skimmer and possibly blocking suction pump which would damage the pool pump itself



Prepared for: Mr & Mrs Somebody 1234 Anywhere Dr

Pool (Continued)





10. Behind home Swimming Pool Pump Motor: Century - Ground wire on pump is not connected, Air bubbles noted in the pumps strainer pot or filter basket this is generally caused from one of three things on the suction side of the pump. One - the pool water level being too low therefore sucking air through the strainer. Two - the rubber O ring in the pump connector coupler being bad or not correctly in place. Three - the clear plastic view cover on the strainer pot not secured tightly. Further evaluation recommended.



11. Behind home Swimming Pool Shut-off Valve: Ball valves - No valve's are labeled for user to know what function they serve, Handle broken





12. Behind home Swimming Pool Heater: Rheem - Not properly grounded, missing ground wire, Would not function, power light came on but did not appear to be heating. Further evaluation by a licensed pool tech is recommended.





13. Behind home Swimming Pool Gauges and Controls: Hayward, Functioning - Broken cover, Damaged needs replaced



Prepared for: Mr & Mrs Somebody 1234 Anywhere Dr


Pool (Continued)





14. Behind home Swimming Pool Ladder/Steps: Stainless steel hanging, Built in step with handrail
 Hanging steps have been removed. built in step handrail is loose, needs to be secured





15. Behind home Swimming Pool Pool Enclosure: Screen cage - Screen cage tension cables are loose and should be tightened. These cables help prevent the cage from moving in windy or bad weather conditions, when this happens it also stretches the screens causing them to become loose or torn. Pool cage door latch requires adjustment to open and close properly. Evidence of water leak noted at cage frame and gutter connection. Dry day unable to verify







Roof

16. Gutters: Aluminum, Boxed - Gutters have some debris (pine needles)in them. Periodic cleaning to maintain proper water flow is recommended, Dry day, unable to check for proper water flow, however no gutters were holding water when observed from roof





17. Leader/Extension: Missing or damaged - Some Splash blocks are missing. installing splash blocks or leaders to move water away from foundation.



Prepared for: Mr & Mrs Somebody 1234 Anywhere Dr

Roof (Continued)





Garage/Carport

18. Front of home Garage Service Doors: Fiberglass with wood core - Entry door not rated for fire, door should be Solid Wood or Metal and preferably have a self closing hinge installed for safety reasons



Laundry Room/Area

19. Inside main Laundry Room/Area Laundry Tub: PVC - No hot water only warm, requires further review



Bathroom

20. Pool bath Bathroom Windows: Wood casement - The window will not open, blocked with shutters or shutter hardware







Prepared for: Mr & Mrs Somebody 1234 Anywhere Dr

Marginal Summary (Continued)

21. Pool bath Bathroom Shower/Surround: Tile pan and tile surround - Cracked grout in corners of shower surround, this is typical of cement based grout being used for corner applications due to expansion and contraction. Recommend replacing with grout "caulk" to help prevent moisture intrusion. Grout caulk can be located in the tile section at most hardware stores



22. Guest/Hallway Bathroom Shower/Surround: Tile pan and tile surround - Cracked grout in corners of shower surround, this is typical of cement based grout being used for corner applications due to expansion and contraction. Recommend replacing with grout "caulk" to help prevent moisture intrusion. Grout caulk can be located in the tile section at most hardware stores



23. Master Bathroom Shower/Surround: Tile pan and tile surround - Cracked grout in corners of shower surround, this is typical of cement based grout being used for corner applications due to expansion and contraction. Recommend replacing with grout "caulk" to help prevent moisture intrusion. Grout caulk can be located in the tile section at most hardware stores, Steamer for shower was not in use at time of inspection. Note on main electrical panel to leave steamer breaker in OFF position. Steam unit is located in attic. Touch control pad in bathroom shower shows signs of corrosion. Further evaluation by a licensed plumbing contractor is recommended.











Prepared for: Mr & Mrs Somebody 1234 Anywhere Dr

Bathroom (Continued)









Bedroom

24. Master Suite, Attached baby room/office Bedroom Doors: Hollow wood, Bi-fold, Pocket slider - Lock/latch on bottom of French door does not work, left side of door cannot be opened. May just need to be cleaned and lubricated. Requires further review



25. Master Suite, Attached baby room/office Bedroom Windows: Wood casement, Non-opening - The window will not open, blocked by shutter or shutter hardware





Prepared for: Mr & Mrs Somebody 1234 Anywhere Dr

Defective Summary

This summary is not the entire report. The complete report may include additional information of concern to the client. It is recommended that the client read the complete report.

Lots and Grounds

 Driveway: Stamped Concrete - Uneven settling, Heaves in concrete causing trip hazard, Damaged or deteriorated, recommend estimate for repair or replacement by a licensed contractor













2. Walks: Concrete - Soil erosion noted along edge of concrete slab on side of garage, slab is cracked, this should be replaced to prevent further undermining of surface and causing more damage to slab



3. Lawn Sprinklers: Front and back yard - Inoperative at time of inspection, tested using manual mode of timer. Timer not tested, pump zone start relay appears to be defective and was making a loud buzzing noise. Sprinkler line(s) and or head damage noted, I recommend a qualified irrigation contractor go through entire sprinkler system, evaluate and or repair all that is needed for proper operation, adjust/repair all sprinkler heads, and educate the new homeowner of proper operation.















Prepared for: Mr & Mrs Somebody 1234 Anywhere Dr

Defective Summary (Continued)

Exterior Surface and Components

4. Exterior Electric Outlets: 110 VAC - Inoperative at time of inspection, Outlets have visible corrosion, Loose or missing moisture cover







Pool

5. Behind home Swimming Pool Type: In ground with spa - Blower for spa jets does not work, pump air jet adjustment cap on spa deck is missing. Appears that individual pump timers for spa and pool are tied into one main timer. Did not locate child safety screens for pool deck protection. Check with current owner if possible. A licensed pool company is recommended to go through and evaluate complete system and specify what all needs repaired for proper operation











6. Behind home Swimming Pool Pool Light Submersed - Pool and spa light did not come with switch, Water/rust stains noted at bottom of pool light. Further evaluation by a qualified pool tech is recommended



7. Behind home Swimming Pool Heater: Rheem - Not properly grounded, missing ground wire, Would not function, power light came on but did not appear to be heating. Further evaluation by a licensed pool tech is recommended.



Prepared for: Mr & Mrs Somebody 1234 Anywhere Dr

Pool (Continued)





Fireplace/Wood Stove

8. Family Room Fireplace Damper: Metal - Damper latch is missing or broken, cannot secure damper in closed position to prevent conditioned air in home from escaping through chimney flue when not in use



Bathroom

9. Master Bathroom Shower/Surround: Tile pan and tile surround - Cracked grout in corners of shower surround, this is typical of cement based grout being used for corner applications due to expansion and contraction. Recommend replacing with grout "caulk" to help prevent moisture intrusion. Grout caulk can be located in the tile section at most hardware stores, Steamer for shower was not in use at time of inspection. Note on main electrical panel to leave steamer breaker in OFF position. Steam unit is located in attic. Touch control pad in bathroom shower shows signs of corrosion. Further evaluation by a licensed plumbing contractor is recommended.



















Prepared for: Mr & Mrs Somebody

1234 Anywhere Dr

Defective Summary (Continued)

Bedroom

10. Left front guest Bedroom Windows: Wood casement -Will not open-requires correction, window crank is broken





